

04 October 2022

# **OVERVIEW OF UPDATES**

# STANDARD SPECIFICATION FOR ROADWORKS V5.1

The significant updates to the Standard Specification for Roadworks V5.1 are shown below.

# **FEEDBACK**

If you have any suggestions for improvement, such as additional or modified text for the Roadworks specification,

Table - Ov	Table – Overview of Updates to Roadworks Specifications – SSRw v.5.1 - 18 July 2022			
CLAUSE	-	CHANGE		
08 SPRAY S	EALING			
8.4.8	Materials – Polymer modified bitumen	Minor edits to 2 notes in 2 tables. (Done 04Oct2022)		
8.21	Price adjustment for bitumen	Date for applicable price indices/indexes changed to date of tender close. GST to be applied to monetary values stated in referenced indices/indexes. Monetary values to be rounded to two decimal places.		

## STANDARD SPECIFICATION FOR ROADWORKS V5.0

The significant updates to the Standard Specification for Roadworks V5.0 are shown below.

#### **FEEDBACK**

If you have any suggestions for improvement, such as additional or modified text for the Roadworks specification, please contact the Manager Specification Services via <a href="mailto:specification.services@nt.gov.au">specification.services@nt.gov.au</a>

### **UPDATES**

Table - Ove	Table – Overview of Updates to Roadworks Specifications – 10 March 2022				
CLAUSE		CHANGE			
Definitions ex	panded and tabulated at each work	section.			
	RLs updated. Legislation references				
		andings – all subsequent work sections renumbered.			
Some clauses	s and sub-clauses moved within the	e specification.			
01 MISCELL	ANEOUS PROVISIONS				
	Utilities and other services				
1.16	passing under existing	New clause - Directional boring mandated.			
	pavements				
1.18	Work near traffic count stations or near culweigh stations	Culweigh stations added.			
	of flear culweigh stations	Requirement for Contractor to verify site levels match			
1.20	Control station check survey	levels on drawings.			
1.21	Surveys and setting out	New clause – added in lieu of selection via TDO			
1.22	Survey pegs	New clause – added in lieu of selection via TDO			
	Documents to be submitted to				
1.30.2	Technical Records, and to	New clause – manuals and permits to be submitted			
	Superintendent				
1.30.3	Warranties	New clause – warranties to be provided			

Doc ID	Version	Issued	Printed	Page
1.07 Updates Overview–SS Roadworks v5.0	2022.08	18 July 2022	4/10/2022	1 of 6





CLAUSE		CHANGE		
1.30.4	Certificates of compliance	New clause – certificates to be provided		
1.30.5	Compliance – Traceability of components	New clause – ensure compliant components used		
1.30.6	List of plant and equipment installed	New clause – list(s) to be provided		
	ION FOR TRAFFIC			
		section. Not all changes are listed below.		
	Tranges made imoughout the work s	Traffic control for Conformance Testing activities		
2.1	General	specified		
2.1.1	Duty of Care	New clause		
2.1.2	Risk Management	New clause		
2.2	Standards and publications	Austroads Guide to Temporary Traffic Management, Code of Practice for Construction Work, and Code of Practice for Excavation Work referenced		
2.5	Workzone traffic management	NT Workzone Traffic Management ID Card mandated. Qualification in safe work in construction industry mandated. Course code and Units of Competency codes updated.		
	Excavations, stockpiles, and	Austroads Guide to Temporary Traffic Management		
2.16	gradients within work zones	cited. Requirements for stockpiles and/or dumped		
	and clear zones	material, made explicit.		
2.17	Temporary pavement marking	Requirements made explicit.		
03 CLEARII	NG GRUBBING AND REHABILITA			
		No changes		
04 EARTHV	NOPKS			
		Material properties definition added. Subgrade		
4.3	Definitions	compaction requirement added to definition.		
4.6	Fill material	Material properties differentiated from properties of completed works. Material to be free of organic matter.		
4.8	Earthworks for drainage	Requirements made explicit.		
		Reference to new table in PAVEMENTS AND		
4.16.2	Conformance - Tolerances	SHOULDERS.		
OF CONFOR	DMANOE TECTINO			
	RMANCE TESTING	Troffic Control for Conformance Testing assertion		
5.1	General	Traffic Control for Conformance Testing mandated.		
5.11	Lot Testing - Table – Dry density ratios for conformance	Compaction for subgrade abutting existing pavemen made explicit		
	density ratios for commentation	That oxplicit		
06 PAVEME	ENTS AND SHOULDERS			
6.2	Definitions	Material properties definition added. Subgrade		
U.L		compaction requirement added to definition.		
6.3.1	Material Properties – Natural Gravel – Table – Natural Gravel Properties	Made explicit that shoulder material is unsealed		
6.7	Pavement acceptance	Guide Note on pavement acceptance cited		
6.7.8	Pavement acceptance – Other tolerance requirements	Requirements made explicit for where new works abut existing works.  Other requirements made explicit.		
		New Table – Relative height tolerances for new works abutting existing works.		
07 STABILI	SATION AND MODIFICATION	1		
		No changes		

ſ	Doc ID	Version	Issued	Printed	Page
ſ	1.07 Updates Overview-SS Roadworks v5.0	2022.08	18 July 2022	4/10/2022	2 of 6





CLAUSE		rks Specifications – 10 March 2022  CHANGE		
CLAUSE		CHANGE		
08 SPRAY	SFALING			
8.1	Standards, Codes, Guides, Test Methods, and Acts	List of applicable documents updated and expanded		
8.3	Scope	Under path growth inhibitor added to specification.		
8.4.8	Material requirements – Polymer modified binder	Quality Assurance requirements made explicit.  New/updated Table – Properties of PMBs for sprayed sealing applications.  New Table-Properties of field-produced crumb rubber binders.  New specification content for crumb rubber. New Table- Properties of crumb rubber.		
8.4.9	Material requirements - Geofabric	New specification content		
8.5	Sprayers and personnel	AP-T262/14 cited.		
8.6	Final preparation of pavement surface	Requirements regarding dampening made explicit.		
8.7	Setting out	Inclusion of widenings made explicit.		
8.8.1	Binder coat requirements - General	Significant new content.  New/updated Table – Binder type requirements - General		
8.8.2	Binder coat requirements – Prime, primer seals, seals, pre- coats, and enrichment coats	Seals and pre-coats added. Emulsion primes added.		
8.8.3	Binder coat requirements – Straight run binder coats	Requirements made explicit.		
8.8.4	Binder coat requirements – PMB coats	SAMI added		
8.9.5	Binder coat requirements – Collection of samples	Sampling points requirements made explicit.		
8.9.6	Binder coat requirements – Sample identification	Requirement to provide samples daily made explicit.		
8.10.1	Stockpile sites	Requirements for stockpiles in rural areas made explicit.		
8.11	Precoating aggregate	Requirements for precoating SAMI aggregates added		
8.13	Spraying	Requirement to allow for different spray rates for different traffic lanes or paths of travel in the same section of roadway		
8.13.3	Spraying – Application spray rates	URL added for DIPL Technical Directive about AGPT 4K. Significant changes to clause.		
8.13.6	Sprayer run	Requirements related to distribution, and to blocked jets, made explicit.		
8.14	Application of geofabric	Significant changes to content.		
8.15	Application of aggregate	Time delays permitted if extreme road surface temperatures are encountered.		
8.17	Waste material	Fourth sweep specified		
8.20.1	Bitumen equivalent volumes	Two new tables.		
8.21	Price adjustment for bitumen	New clause		
09 DENSE	GRADED ASPHALT	<u></u>		
9.2	Standards and publications	ATS 3110 cited. ATM 453 cited. Bituminous rise and fall standard cited.		
9.3	Definitions	Material properties definition added.		
9.4	Asphalt mix design	Clause relocated.  Requirements for registration of mix design made explicit.		

Doc ID	Version	Issued	Printed	Page
1.07 Updates Overview–SS Roadworks v5.0	2022.08	18 July 2022	4/10/2022	3 of 6



CLAUSE		CHANGE
9.5.1	Traffic categories – Under path	New clause
	growth inhibitor	Name alama
9.6.4	Materials - RAP	New clause
9.7	Binders	New/updated clause
9.8	Sampling of binder	New/updated clause New clause
9.9	Paving plans Surface preparation – Cold	New clause
9.10.3	planing	Maximum cutting speed specified
9.10.6	Surface preparation – Tack coat	Requirements made explicit
9.14.6	Compaction – Joint compaction	Requirements for compliance made explicit
9.15.2	Conformance – Process testing	Requirements made explicit
9.15.3	Conformance – Finished pavement properties	ATM 453 cited in Table – Surface shape requirements.  Table – Relative height tolerances for new works abutting existing works in PAVEMENTS AND SHOULDERS cited
9.16	Price adjustment for bitumen	New clause
10 SLURRY	SURFACING	
		No changes
-		
	LANEOUS CONCRETE WORKS	
11.3.6	Materials - Reinforcement	Plastic reinforcement supports specified
11.3.8	Materials – Under path growth inhibitor	New clause
12 DRAINA	GE WORKS	
	Construction of culverts and	Backfill stabilisation with cement specified for full
12.6.10	structures - Backfill	width between headwalls
13 PROTEC	CTION WORKS	
		No changes
14 ROAD F	URNITURE AND TRAFFIC CONTR	OL DEVICES
14.4	Tactile ground surface indicators	Clause re-written – all new content.
440		Steel flexible guide posts and Testing split off to
14.6	Plastic flexible guide posts	separate clauses
14.7	Steel flexible guide posts	New clause
14.8	Testing of flexible guide posts	New clause
14.9.3	Road signs – Remotely activated road condition information signs	New clause
14.9.4	Road signs - Materials	New Table – Roadside signs – Mounting selection
14.9.7	Road signs - Installation	Clause rewritten
14.9.8	Road signs – Reinstatement and relocation of existing signs	Clause rewritten
14.12.3	Road safety barriers – Steel beam guardrail system - Installation	Requirement for delineators added
14.13	Road safety barriers – Steel wire rope system	Requirement for delineators added
	AMPS AND BARGE LANDINGS	New work section

Doc ID	Version	Issued	Printed	Page
1.07 Updates Overview–SS Roadworks v5.0	2022.08	18 July 2022	4/10/2022	4 of 6





CLAUSE		CHANGE
16.4	Contractor accreditation	Exemption limitations made explicit
-		Table – Dimensional tolerances for pavement
40.0	Pavement marking	markings – Tolerance is zero if no value in table -
16.9	conformance tolerances	Requirements for aerodromes differentiated from
		other locations
16.11	Thermoplastic materials	Approver amended
16.12	Cold applied plastic materials	Approver amended
16.13	Audio tactile line marking	Approver amended
10.13	Addio tactile line marking	Approver amended
17 LANDS	CAPE	
		No changes
40 DUCTIN	IC AND CONDUITS	
18 DUCTIN	IG AND CONDUITS	Services to cross below existing pavements clause in
18.1	Cross references	MISCELLANEOUS PROVISIONS cited
		MIGGELEANEGOST NOVISIONS GREG
19 TRAFFI	C CONTROL SIGNALS AND INTEL	LIGENT TRANSPORT SYSTEMS
19.1	Cross references	Services to cross below existing pavements clause in
19.1		MISCELLANEOUS PROVISIONS cited
19.2.3	Standards and publications –	New content added to table
	Civil standard drawings	
20 TR AFFI	C COUNTING STATIONS	
ZU IIIAIII		Services to cross below existing pavements clause in
20.1	Cross references	MISCELLANEOUS PROVISIONS cited
00.0.0	Standards and publications –	
20.2.2	Civil standard drawings	New content added to table
04 OTDEE	F. LOUTING	
21 SIREE	<u> </u>	Comittee to come heless estation necessaries also a fi
21.2	Cross references	Services to cross below existing pavements clause in
		MISCELLANEOUS PROVISIONS cited
22 DIRECT	IONAL BORING	<u> </u>
		Services to cross below existing pavements clause in
22.2	Cross references	MISCELLANEOUS PROVISIONS cited
23 PROTE	CTIVE COATINGS	
		No changes
24 MEASII	REMENT AND PAYMENT	
24.2.3	Gravelling of detours	Maintenance and rehabilitation included
24.7.2	Supply and spread binder	In-situ methods
24.7.2	Spray sealing	Reference to Rise and fall added
	Under noth growth inhibitor	New item
24.8.2	Under path growth inhibitor	New item
24.9.2	Dense graded asphalt - Under	New item
	path growth inhibitor Miscellaneous concrete -	
24.11.1	Footpaths	Under path growth inhibitor added
24.15	Boat ramps and barge landings	New clause for new work section
	Pavement marking – Line	Measurement method altered for chevrons and
24.16.3	markings	speed humps
	<del>y</del>	
25 REFERI	ENCED AUSTRALIAN STANDARDS	
		Additional citations added to table

Doc ID	Version	Issued	Printed	Page
1.07 Updates Overview-SS Roadworks v5.0	2022.08	18 July 2022	4/10/2022	5 of 6





Table – Overview of Updates to Roadworks Specifications – 10 March 2022			
CLAUSE	CHANGE		
	Austroads Guide to Temporary Traffic Management (AGTTM), BS 1881, IALA E-108, IALA E-200-1 added to table		
27 ACTS, REGULATIONS, CODES, A	ND AUTHORITIES		
,	No changes		
28 CIVIL STANDARD DRAWINGS FO	DR ROADWORKS		
	Traffic signals related CS drawings added to table		
29 NORTHERN TERRITORY CLIMAT	E ZONES TABLE		
	No changes		
30 HOLD POINTS AND WITNESS PO	INTS SCHEDULES		
	Updated		
31 UPDATES OVERVIEW			
	New updates overview		

Doc ID	Version	Issued	Printed	Page
1.07 Updates Overview–SS Roadworks v5.0	2022.08	18 July 2022	4/10/2022	6 of 6